

Project: **Supply of Materials, Labor and Equipment for the Derusting, Repainting and Renumbering of Bollards at Port of Cagayan de Oro**

Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
------	-------------	----------	------	-----------	--------

1.0	Derusting and cleaning of bollards	1.00	lot		
-----	------------------------------------	------	-----	--	--

Work Description

Supply of Labor and Equipment for the Derusting, and cleaning of Bollards from Lagoon 1-2, and Berth 1-10

Materials

Rust Converter	5.00	gal		
Steel Brush	15.00	pcs		
Paint Brush 2"	10.00	pcs		

Equipment

1 Electric Demolition Hammer	14.00	days		
------------------------------	-------	------	--	--

Manpower

1 Foreman	14.00	days		
5 Unskilled Labor	14.00	days		

ESTIMATED DIRECT COST	P=	
ESTIMATED INDIRECT COST	P=	
TOTAL COST OF WORK ITEM 1	P=	

2.0	Repainting and numbering of bollards	1.00	lot		
-----	--------------------------------------	------	-----	--	--

Work Description

Supply of Materials, Labor and Equipment for Repainting and Renumbering of Bollards from Lagoon 1-2, and Berth 1-16

Materials

Elastomeric Paint - Light Beige	24.00	Gal.		
Elastomeric Paint - Denim Blue	6.00	Gal.		
Concrete Epoxy Primer White	19.00	Gal.		
Epoxy Enamel Aluminum -890	6.00	Gal.		
Epoxy Primer Gray-850	4.00	Gal.		
Aqua Epoxy Light Blue	5.00	Gal.		
Epoxy Enamel Ultra Marine Blue	3.00	Gal.		
8" Paint Roller w/ Tray	10.00	Set		
4" Paint Metal Scrapper w/ Handle	10.00	Pc.		
2" Paint Brush	10.00	Pc.		
Reflectorized Traffic Paint Yellow	1.00	Gal.		
Baby Roller	5.00	Pc.		
8" Waste Pad	5.00	Kilo		

Equipment

Manpower

1 Foreman	11.00	day(s)		
3 Skilled Worker	11.00	day(s)		
3 Unskilled Worker	11.00	day(s)		

ESTIMATED DIRECT COST	P=	
ESTIMATED INDIRECT COST	P=	
TOTAL COST OF WORK ITEM I.2	P=	
	-	
TOTAL AMOUNT	P=	

Prepared by:

Name & Signature
Designation: _____
Date: _____