

CANVASS FORM:

Project: Supply of Materials, Labor and Equipment for the PWD Facilities at PTB and Amenity Building

Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
------	-------------	----------	------	-----------	--------

1.0	Repainting of PWD Drop-off Area and Parking Space	6.00	units		
-----	---	------	-------	--	--

Work Description

To supply of materials, Labor and equipment for the repainting of PWD drop-off area and parking space

Materials

Epoxy Primer White	3.00	gal		
Epoxy Reducer	3.00	gal		
Reflectorized Traffic Paint White	3.00	gal		
Epoxy Enamel Blue	3.00	gal		
1/4" Ordinary plywood	1.00	pc		
7" Paint Roller w/ Tray	2.00	pc		
Baby Roller Cotton w/ tray	2.00	pc		
2" Paint Brush	2.00	pc		
3" Paint Brush	2.00	pc		
Lacquer Thinner	1.00	gal		
8" dia. Waste Pad	1.00	kilo		
Paint thinner	1.00	gal		
sub-total . . .				

Equipment

Manpower

1 Foreman	3.00	day(s)		
3 Skilled Labor	3.00	day(s)		
3 Unskilled Labor	3.00	day(s)		
sub-total . . .				

ESTIMATED DIRECT COST	
ESTIMATED INDIRECT COST	
TOTAL COST OF WORK ITEM 1	

2.0	Supply of Materials, Labor and Equipment for the PWD Facilities at PTB and Amenity Building	1.00	lot		
-----	---	------	-----	--	--

Work Description

To supply of materials, labor and tools for the installation of PWD comfort room accessories

Materials

0.6m x 1-1/2" stainless Grab Bar	10.00	pc		
Door knob	2.00	pc		
stainless p-trap w/ cleanout	2.00	pc		
1/2" stainless bidet with accessories	10.00	pc		
1/2x1/2x1/2 two-way angle valve	10.00	pc		
Bathroom hook	10.00	pc		
0.45mx0.5mx4mm vanity mirror	10.00	pc		
sub-total . . .				

Equipment

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
Manpower					
1	Foreman	3.00	day(s)		
3	Skilled Worker	3.00	day(s)		
3	Unskilled Worker	3.00	day(s)		
				sub-total . . .	
				ESTIMATED DIRECT COST	
				ESTIMATED INDIRECT COST	
				TOTAL COST OF WORK ITEM 2	

3.0	Fabrication of Aluminum Cladding Signages	1.00	lot		
-----	---	------	-----	--	--

Work Description

To supply of materials, labor and equipment for Fabrication of Signages

Materials

Portland Cement	2.00	bag		
Washed Sand	0.50	cu.m		
1-1/2" Galvanized Steel Pipe 6m	4.00	pc		
4'x8'x3mm Aluminum Cladding	3.00	pc		
5/16x3" Carriage bolt with nut & washer	24.00	pc		
10mm dia.deformed bar	2.00	pc		
0.3mm G.I Plain sheet	1.00	pc		
Ga.18 Tie Wire	2.00	kl		
4"dia.x0.04"x5/8" Cutting Disk	1.00	box		
Epoxy primer Gray	1.00	gal		
Epoxy reducer	1.00	gal		
Quick Dry Enamel Lemon Yellow	1.00	gal		
2" Paint brush	2.00	pc		
Vinyl Label Sticker Sign Water Proof-:				
RESERVED PARKING PWD	2.00	pc		
ALL GENDER PWD RESTROOM	2.00	pc		
PWD PRIORITY SEATING WAITING AREA	6.00	pc		
PWD PRIORITY LANE	4.00	pc		
PWD DROP OFF AND PICK-UP ONLY	3.00	pc		
			sub-total . . .	

Equipment

Manpower

1	Foreman	3.00	day(s)		
3	Skilled Labor	3.00	day(s)		
3	Unskilled Labor	3.00	day(s)		
				sub-total . . .	
				ESTIMATED DIRECT COST	
				ESTIMATED INDIRECT COST	
				TOTAL COST OF WORK ITEM 3	

TOTAL BID AMOUNT .....

Prepared by:

\_\_\_\_\_  
Name & Signature  
Designation: \_\_\_\_\_  
Date: \_\_\_\_\_