

Project: **Maintenance of Pedestrian Lanes, Center Lines, Curbs and Parking Areas Baseport and Terminal Ports (MPF-MOC-03-2025)**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
------	-------------	----------	------	-----------	--------

1.	Reflectorized Thermoplastic Pavement Markings	565.19	SQ.M.		
----	---	--------	-------	--	--

Work Description					
Provide necessary labor,materials and equipment for the maintenance of the pedestrian lane using thermoplastic pavement markings at the Port of Cagayan de Oro					
Materials					
Thermoplastic Paint (White) 25kg	184.00	bag			
Glass Beads	19.00	bag			
Primer	68.00	liter			
LPG (50kg)	2.30	cyl.			
LPG (12kg)	1.20	cyl.			
Calsumine	71.00	kg			
Miscellaneous	1.00	lot			
Equipment					
1 - Portable grinder	3.00	days			
1 - Applicator Machine	3.00	days			
1 - Kneading Machine	3.00	days			
Minor tools					
Manpower					
1 - Foreman	3.00	days			
2 - Skilled Labor	3.00	days			
6 - Unskilled Laborer	3.00	days			
ESTIMATED DIRECT COST				P	
ESTIMATED INDIRECT COST				P	
TOTAL COST OF WORK ITEM 1.				P	

2.	Reflectorized Thermoplastic Pavement Markings	164.81	SQ.M.		
----	---	--------	-------	--	--

Work Description					
Provide necessary labor,materials and equipment for the maintenance of the pedestrian lane using thermoplastic pavement markings at the Port of Balingoan					
Materials					
Thermoplastic Paint (White) 25kg	54.00	bag			
Glass Beads	6.00	bag			
Primer	20.00	liter			
LPG (50kg)	0.79	cyl.			
LPG (12kg)	0.50	cyl.			
Calsumine	21.00	kg			
Miscellaneous	1.00	lot			
Equipment					
1 - Portable grinder	2.00	days			
1 - Applicator Machine	2.00	days			
1 - Kneading Machine	2.00	days			
Minor tools					
Manpower					
1 - Foreman	2.00	days			
2 - Skilled Labor	2.00	days			
6 - Unskilled Laborer	2.00	days			
ESTIMATED DIRECT COST				P	
ESTIMATED INDIRECT COST				P	
TOTAL COST OF WORK ITEM 2.				P	

AMOUNT IN WORDS :
